



Town of East Hartford

ADDENDUM N^o. 1

**HOCKANUM PARK PICKLEBALL COURTS
Bid No. 21-10**

Issued January 25, 2021

The following summarizes revisions to the Bid Documents included in Addendum N^o. 1 for the HOCKANUM PARK PICKLEBALL COURTS (Bid No. 21-10).

- The pre-bid meeting was on Wednesday, January 20, 2021. Questions raised at the pre-bid meeting, and responses, follow:

1. How do I contact Sara Ross from the Grants Department?

Answer: Sara can be reached at (860) 291-7210 or sross@easthartfordct.gov.

2. How do I find the certified payroll form?

Answer: Link to certified payroll form:

<http://www.dol.gov/whd/forms/wh347.pdf>

Link to directions on how to complete certified payroll form:

<http://www.dol.gov/whd/forms/wh347instr.htm>

Link to Contractor's Guide to Prevailing Wage Requirements for Federally-Assisted Construction Projects: Making Davis-Bacon Work:

<https://www.hudexchange.info/resource/2541/making-davis-bacon-work-contractors-guide-prevailing-wage-requirements/>

3. Is the Town providing a dumpsite?

Answer: The Town will provide a dumpster on site for metal disposal. Concrete and bituminous will have to be disposed of by the contractor per the contract. Any suitable base material can be brought to the Ecology Drive Transfer Station.

4. Am I allowed to bid on this project as a prime contractor, assuming we can provide specialty subcontractors that meet the requirements for completing Section 4.20 as well as section 14.01 of the project?

Answer: Yes. Please see revision on page 149 of the Bid Specifications.

The following documents & drawings are attached and included in Addendum N^o. 1:

Revised Bid Documents

- Replace page 149.

End of Addendum N^o. 1

SECTION 4.20 POST-TENSIONED CONCRETE (Cont'd)

- i. Wet cure concrete slab for a minimum 7 days or until final stress.

LAYOUT AND PLACEMENT:

Prior to installation of furnishings, locate in field and review with Engineer/Landscape Engineer for siting, alignment and grade relationships prior to placement. Subbase grading and compactions of pavement bases shall be laser graded and verified by a Connecticut Registered Professional Surveyor. Final bituminous concrete paving shall be installed and laser set grades shall be certified by a Connecticut Registered Professional Surveyor as meeting the grades required before the start of the installation of fencing and the synthetic court surfaces.

CONTRACTOR QUALIFICATIONS:

The Contractor and/or Subcontractor must have a minimum three (3) years of documented experience in the construction of tennis or basketball courts.

The Contractor and/or Subcontractor must have a minimum three (3) years of documented experience in post-tension concrete construction.

The Contractor must provide a minimum of three (3) references from other municipalities or public agencies where similar work was done. References shall be shown in the "Qualifications of Bidder" section and submitted with the bid.

The Contractor must be certified by the Post-Tension Concrete Institute with a minimum level 1 certification for installation.

SUBMITTALS:

The Contractor shall submit engineered drawings, certified and stamped by a professional engineer, for the design of the post tension concrete slab. The design shall meet Post-Tension Concrete Institute requirements for slab on grade and include:

- i. Cable layout and spacing with calculations
- ii. Details showing live and dead ends
- iii. Court material cross section
- iv. Concrete mix design and placement sequence
- v. Stressing sequence

The Contractor shall submit approved stressing reports to the Engineer.

Prior to pouring the concrete court slab, the Contractor shall supply to the Engineer an inspection report certifying that the installed cable installation meets the Post-Tensioning Institute requirements for slab on grade construction. The report shall be signed and certified by a registered professional engineer or a Level 2 Unbonded PT Inspector as certified by the Post-Tensioning Institute.