



Town of East Hartford

ADDENDUM N^o. 02

**Pitkin Street Sidewalk Replacement (Meadow Street to Darling Street)
Bid No. 23-22**

Issued April 5, 2023

The following summarizes revisions to the Bid Documents included in Addendum N^o. 02 for the Pitkin Street Sidewalk Replacement (Meadow Street to Darling Street) (Bid No. 23-22).

- **SECTION 8.14 RESET STONE CURB** and **SECTION 9.50 TURF ESTABLISHMENT** under the special provisions have been changed.
 - **TURF ESTABLISHMENT** will be paid per square feet and is reflected in the **SECTION 9.50**.
 - **RESET STONE CURB** now includes the bituminous asphalt and will be paid under ITEM# 814001.

The following documents & drawings are attached and included in Addendum N^o. 02:

Revised Bid Documents

- Replace Page 129 with the attached document **Addendum 2- Section 8.14 Reset Stone Curbing – Page 129**.
- Replace Page 142 with the attached document **Addendum 2- Section 9.50 Turf Establishment – Page 142**.

End of Addendum N^o. 02

SECTION 8.14- RESET STONE CURBING

8.14.01—Description: This work shall consist of the removing and resetting or adjusting of existing stone curbing to the lines and grades given, in accordance with the dimensions and details of the plans or as ordered and in conformity with these specifications.

This work shall also include the production, delivery, placement and compaction of a uniform textured, non-segregated, smooth bituminous concrete pavement to the grade and tack coating as shown on the plans.

8.14.02—Materials: All existing curbing which is acceptable shall be used. The reset stone curbing shall be in lengths of not less than 4 feet long, except where necessary for closures, where no piece shall be less than 3 feet long. Mortar for this work shall be as specified in M.11.04.

All bituminous materials shall meet the requirements of M.04. Recycled materials may not be used.

8.14.03—Construction Methods: The construction methods for this work shall meet the requirements of 8.13.03 for stone curbing, as supplemented by the following requirements:

The curbing to be reset shall be removed with care to avoid damage and, if ordered, shall be transported to a point or points on the project which will allow all the reset curbing to be installed in continuous lines.

Curbing removed and not reset shall remain the property of the State unless otherwise ordered by the Engineer and shall be transported to such points, adjacent to the work, as the Engineer may designate. Where adjustments only have to be made to curbing, such adjustments shall be carried out as specified by the Engineer.

All paving methods shall can be found on section 4.06.03.

8.14.04—Method of Measurement: This work will be measured for payment by the actual number of linear feet of the class of curbing, reset and accepted. Measurement shall be made along the top arris line of face of curb.

8.14.05—Basis of Payment: This work will be paid for at the Contract unit price per linear foot for "Reset Curbing," complete in place, which price shall include all materials *including furnishing and placing of bituminous concrete*, equipment, tools and labor incidental thereto and all excavation, backfilling, disposal of surplus material and all drainage openings.

There will be no direct payment for furnishing, placing and compacting granular base, beveling or rounding the ends of the curbing, sealing the joints with mortar, removing the curbing and hauling it to any location on or adjacent to the project as directed by the Engineer; but the cost of this work shall be considered as included in the general cost of the work.

<u>ITEM NO.</u>	<u>DESCRIPTION</u>	<u>UNIT</u>
ITEM #814001	RESET GRANITE CURB	LF

SECTION 9.50 TURF ESTABLISHMENT (Cont'd)

the turf establishment operations on the shoulders, pavement, and/or elsewhere on adjacent properties publicly and privately owned.

7. Erosion Control Matting: Erosion control matting shall be installed following seeding where called for on the plans or as directed by the Engineer. Staples shall be installed as per Manufacturer's recommendations. Where two lengths of matting are joined, the end of the upgrade strip shall overlap the down-grade strip. The Contractor shall maintain and protect the areas with erosion control matting until such time as the turf grass is established. The Contractor shall replace or repair at their own expense any and all erosion control matting areas damaged by fire, water or other causes including the operation of construction equipment. No mowing will be required in the locations where erosion control matting is installed.

9.50.04—Method of Measurement:

This work will be measured for payment by the number of square feet of surface area of accepted established perennial turf grass.

9.50.05—Basis of Payment:

This work will be paid for at the Contract unit price per square feet for “Turf Establishment” which price shall include all materials, mowing, maintenance, equipment, tools, labor and work incidental thereto. Partial payment of up to 60% may be made for work completed, but not accepted.

<u>ITEM NO.</u>	<u>DESCRIPTION</u>	<u>UNIT</u>
ITEM #950005A	TURF ESTABLISHMENT	S.F.