



**Town of East Hartford**

**ADDENDUM N<sup>o</sup>. 01**

**1165-1195 Main Street Sidewalk Replacement  
Bid No. 24-19**

**Issued February 8, 2024**

*The following summarizes revisions to the Bid Documents included in Addendum N<sup>o</sup>. 01 for the 1165-1195 Main Street Sidewalk Replacement (Bid No. 24-19).*

- **Item 811001 - Concrete Curbing** has been added to the bid proposal sheet. Please replace Pages 19 & 20 on the bid documents with the attached.
- **Section 8.11 Concrete Curbing** was included in the Technical Specifications. Please include **Addendum 1- Concrete Curbing Technical Specifications** after Page 142

*The following documents & drawings are attached and included in Addendum N<sup>o</sup>. 01:*

**Revised Bid Documents**

- Replace Pages 19 & 20 with the attached document **Addendum 1- Unit Price Sheet – Page 19 & 20**.
- Include **Addendum 1- Concrete Curbing Technical Specifications** after Page 142.

**End of Addendum N<sup>o</sup>. 01**

TOWN OF EAST HARTFORD  
 BID PROPOSAL SHEET  
 1165-1195 MAIN STREET SIDEWALK REPLACEMENT

BID NO. 24-19				
Item #	Description	Estimated Quantity	Unit Price <i>{in numbers}</i>	Extended Amount <i>{in numbers}</i>
921001	Concrete Sidewalk	3,520 SF	Per SF	
921002	Concrete Sidewalk Ramp	65 SF	Per SF	
811001	Concrete Curbing	160 LF	Per LF	
814001	Reset Stone Curbing	70 LF	Per LF	
586001	Reset Valves, Traffic & Electric Boxes"	9	Each	
1209001	Line Striping	50 LF	Per LF	
970006A	Trafficperson (Uniform Police Officer)	Estimated	N/A	\$9000.00
970007A	Trafficperson (Uniformed Flagger)	160 hours	Per Hour	
<b>GRAND TOTAL OF ALL ITEMS =&gt;</b>				

- A. The undersigned understands that there may be changes, omissions, or modification in the Work, and that appropriate adjustments will be made to the Contract price in accordance with the Contract Documents. The undersigned understands that the Owner reserves the right to accept or reject any or all bids, and to waive all formalities, any irregularities, and accept the Bid deemed to be in the Owner's best interest.
- B. Bid prices shall not include any sales, excise or other taxes for which the Owner is not liable. Town of East Hartford is the awarding authority.
- C. The Bidder agrees to hold the above pricing for sixty (60) days.
- D. The Bidder hereby agrees to commence Work under this Contract within ten (10) days of written Notice to Proceed from the Town, and to complete the Work of all base bid items by MAY 31, 2024 thereafter. The Bidder further agrees to pay as liquidated damages, the sum of FIVE HUNDRED DOLLARS (\$500) for each consecutive calendar day beyond the date of completion. Liquidated damages are not intended as a penalty but rather shall be construed as

a best estimate of damages which the Town will suffer due to Bidder's refusal, failure or neglect to perform pursuant to his Bid and Contract Documents.

- E. The Bid security in the sum of: 5% OF TOTAL BID is to become the property of the Town in the event the above forms are not executed within the time set forth above, as liquidated damages, and not as a penalty for the delay and additional expense to the Town caused thereby.
- F. The Bidder affirms that they understand the obligations of the CHRO minority set-aside requirements outlined in the *Non-Discrimination and Affirmative Action Provisions* included with the Bid Requirements for this RFP.

Respectfully Submitted By:

(Signature) \_\_\_\_\_

Name (Please Print): \_\_\_\_\_

Title: \_\_\_\_\_

Company: \_\_\_\_\_

Business Address: \_\_\_\_\_

\_\_\_\_\_

Business Phone: \_\_\_\_\_ ( ) \_\_\_\_\_

Business Fax: \_\_\_\_\_ ( ) \_\_\_\_\_

Email Address: \_\_\_\_\_

**SECTION 8.11  
CONCRETE CURBING**

**8.11.01—Description:** This item shall consist of concrete curbing, furnished in accordance with the dimensions and details of the plans, and installed to the lines and grades shown on the plans.

**8.11.02—Materials:** All concrete curbing shall be constructed with Class PCC04460 Concrete as defined in M.03.02.

Precast curbing shall meet the requirements of M.08.02-4.

Joint filler shall meet the requirements of M.03.08-2.

Base material, if required, shall meet the requirements of M.02.01, M.02.02 or M.05.01.

**8.11.03—Construction Methods:** Construction methods shall meet the requirements of 6.01.03, as supplemented by the following:

**1. Excavation:** Excavation shall be made to the required depth, and the base upon which the curbing is to be set shall be compacted to a firm, even surface.

**2. Section Lengths and Joints:** All straight curbing sections shall be uniform length and a minimum of 8 feet.

Curved curb section lengths may vary with radii of curves.

When a gap of less than 8 feet is required for closure, the length of curbing may be varied, but no section less than 2 feet will be permitted.

For both precast and cast-in-place concrete curbing, a 1/2 inch joint shall be filled with joint filler at intervals of approximately 50 feet, and contraction joints shall be placed at intervals of approximately 15 feet.

**3. Cast-In-Place Curbing:** Forms shall be clean and founded on a moist, firm, unfrozen base and the curbing shall be constructed so that the exposed faces may be accessed before the concrete has taken final set to allow finishing. Cast-in-place curbing shall be finished in accordance with 6.01.03-II-10(b).

**4. Precast Concrete Curbing:** The Contractor shall stabilize the precast concrete curbing during installation until backfilling is complete.

Precast curbing set on a radius of 50 feet or less shall be fabricated to the required radius within the manufacturer's tolerance..

**5. Backfilling:** The backfill shall consist of approved material placed in 6 inch layers and each layer shall be thoroughly compacted. The final elevation of the backfill shall match the lines shown on the plans or as ordered by the Engineer.

**8.11.04—Method of Measurement:** This work will be measured for payment along the top of the curb and will be the actual number of linear feet of concrete curbing completed and accepted.

**8.11.05—Basis of Payment:** Payment for this work will be made at the Contract unit price per linear foot for "Concrete Curbing" of the type specified, complete and accepted in place, which price shall include all excavation, materials, equipment, tools, backfilling, disposal of surplus material, and labor incidental thereto.

There will be no direct payment for furnishing, placing and compacting base material, but the cost of this work shall be considered as included in the general cost of the work.

Pay Item	Pay Unit
Concrete Curbing (Type)	l.f.